

5 Moseley's Farm Business Centre Fornham All Saints Bury St Edmunds Suffolk IP28 6JY T: 01284 765391

E: info@treesurveys.co.uk www.treesurveys.co.uk

Trees and Development

A guide to the Commissioning of BS5837:2012 Tree Surveys for prospective development.

As one of the countries leading Arboricultural Consultancy companies we undertake approximately 60 plus tree surveys for development projects every month, a large number of which are requested as urgent as the associated planning application is up and running. This obviously can lead to delays in the planning application as issues not previously considered with regards trees and development are raised.

In order to pre-empt this, and ensure that the relative trees and associated constraints are considered, below is a guide to the 'ideal' scenario, advocated by Hayden's, with regards the commissioning of Tree Surveys and Arboricultural Assessments for prospective development.

The Process can be divided in to 3 main phases. Within these the particular elements of the Arboricultural Assessment can be directly related to the Royal Institute of British Architects (RIBA) Work Stages, as detailed below.

Phase 1 – Feasibility and Planning		
RIBA Work Stage	Arboricultural Assessment Works	
A - Feasibility Study	Topographical Survey	
	BS 5837:2012 Tree Survey commissioned	
B - Design Brief	Preparation of Tree Constraints Plan (TCP)	
C - Conceptual Design	Preparation of Arboricultural Implication Assessment (AIA) in relation to design	
D - Design	Preparation of Arboricultural Implication Assessment (AIA) Preparation of	
Development	Preliminary Arboricultural Method Statement (AMS) and Tree Protection Plan (TPP)	

Phase 2 - Detailed Technical Design	
RIBA Work Stage	Arboricultural Assessment Works
E - Technical Design	Preparation of Arboricultural Method Statement for permitted development
F – Production	and associated services
Information	Preparation of Schedule of Pre Construction Tree Works and Removal
	Finalize Tree Protection Plan (TPP) including Construction Exclusion Zones (CEZ)
G – Tender	Tree Survey, Arboricultural Implication Assessment (AIA), Arboricultural
Documentation	Method Statement (AIA) , Tree Protection Plan (TPP), Construction Exclusion
	Zones (CEZ) and Schedule of tree works and removal to be included in all
	relevant Tender Documentation

Trading as Hayden's Arboricultural Consultants Ltd

Director: Stephen Hayden Registered Company No. 07134016 VAT No. 720 386549



Phases 1 and 2 are an essential part of the planning and pre-commencement stages of development. Once the construction and implementation stage commences it is essential that the arboricultural elements of the permitted development are implemented in order to ensure the future well being of those trees to be retained as part of the permitted development. Given this, it is recommended that the Arboricultural Elements of the project are monitored (Tree Works, Tree Protection and any specialist operations). The benefits of this are two-fold in that, firstly, it should prevent unnecessary damage to trees to be retained and secondly, where trees are accidentally damaged the necessary remedial tree works can be identified, approved and implemented. Such incidents should be recorded on the CDM Health and Safety file to provide proof that the necessary remedial works were undertaken should the tree fail in the future. Consequently, the following is recommended for the final and third stage of development – **Implementation and Aftercare**.

Phase 3 - Implementation and Aftercare	
RIBA Work Stage	Arboricultural Assessment Works
H – Tender Action	Site Meeting with Arboricultural Consultant and tendering Arboricultural Contractors
J – Mobilization	Preparation and approval of Arboricultural Monitoring Program Pre- COmmencement meeting with Project/Site Manager, Local Planning Authority Trees Officer and Arboricultural Consultant
K – Construction to Practical Completion	Implementation of Approved Arboricultural Monitoring and Reporting
L - Post Practical Completion	Final Inspection of Trees and Monitoring Report

If the Arboricultural elements of any prospective developments are undertaken as detailed above, it will, without doubt, enhance the chances of success and prevent any unnecessary delays to the planning process due to trees, thereby saving both time and money.

If you would like to discuss the above or any other tree related issues contact us either at info@treesurveys.co.uk or on 01284 765391

Stephen Hayden

Principal Arboricultural Consultant

